



ROWLAND UNIFIED SCHOOL DISTRICT
 1830 S. NOGALES STREET
 ROWLAND HEIGHTS, CA 91748

ADDENDUM 2
 MATERIALS TESTING LABORATORY SERVICES FOR SOLAR
 SHADE STRUCTURE
 RFQ/P No. 2023/24 (Q12)

MARCH 12, 2024

TO ALL PROSPECTIVE BIDDERS:

Note: *The following Addendum shall become part of the contract documents, and the bidder shall provide for all work as required by this Addendum. Acknowledge receipt of the Addendum on the Bid Proposal Form.*

Specifications/Clarifications:

- Question:** Will the District release the soils report for the project? Luminace has the soils report
Answer: The following is the link for the soils report:
<https://app.box.com/s/d7i2bxpgsoe9bcq2m4iw2o5shqkzd8v6>
- Questions:** Does the District have a construction schedule for the project?
Answer: Attached is the construction schedule
- Question:** The RFQ/P mentions material testing laboratory services, but the documents provided via the [box.com](#) link include services that differ. Will the District clarify what services are requested for the project?
Answer: The services requested are listed in the DSA 103-22: Listing of Structural Test & Special Inspections (Concrete), 2022 CBC **“Performed by LOR”**

DSA 103-22: LISTING OF STRUCTURAL TESTS & SPECIAL INSPECTIONS (CONCRETE), 2022 CBC

Table 1705A.3; ACI 318-19 Sections 26.12 & 26.13

Application Number: 03-123497	School Name: Giano Intermediate School	School District: Rowland Unified School District
DSA File Number: 19-92	Increment Number:	Date Created: 2023-11-20 14:01:34

C1. CAST-IN-PLACE CONCRETE				
	Test or Special Inspection	Type	Performed By	Code References and Notes
<input checked="" type="checkbox"/>	a. Verify use of required design mix.	Periodic	SI	Table 1705A.3 Item 5, 1910A.1.
<input checked="" type="checkbox"/>	b. Identify, sample, and test reinforcing steel.	Test	LOR	1910A.2; ACI 318-19 Ch.20 and Section 26.6.1.2; DSA IR 17-10. (See Appendix (end of this form) for exemptions.)
<input checked="" type="checkbox"/>	c. During concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete.	Test	LOR	Table 1705A.3 Item 6; ACI 318-19 Sections 26.5 & 26.12.
<input checked="" type="checkbox"/>	d. Test concrete (f'c).	Test	LOR	1905A.1.17; ACI 318-19 Section 26.12.
<input type="checkbox"/>	e. Batch plant inspection:	See Notes	SI	Default of 'Continuous' per 1705A.3.3. If approved by DSA, batch plant inspection may be reduced to 'Periodic' subject to requirements in Section 1705A.3.3.1, or eliminated per 1705A.3.3.2. See IR 17-13. (See Appendix (end of this form) for exemptions.)
<input type="checkbox"/>	f. Welding of reinforcing steel.	Provide special inspection per STEEL, Category S/A4(d) & (e) and/or S/A5(g) & (h) below.		

Responses to RFI's will be provided via addenda posted on the district's website at www.rowlandschools.org

The vendor must check the district's website for any addendum before submitting their proposal.

Rosana McLeod

Director of Purchasing